KADUR DIVISION.

Dated 6th March 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 31st March 1911, for extending and improving the Munsiff's Court at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chickmagalur, between the hours of 11 A.M. to 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for extending and improving Munsiff's Court at Chickmagalur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Royalty to be paid to Government will have to be borne by the contractor.

Items of work	*Per*	*Quantity*
Main building.		
1. Earthwork excavation and filling into basement level ...	C. yd.	71
2. Burnt stone in lime mortar including bond slabs	C. ft.	2,681
3. Burnt brick in lime mortar do	„	4,025
4. Do do arch work	„	145
5. Burnt stone slabs, well dressed	Sq. ft.	401
6. Cutting grooves to up rights	Each	2
7. Plastering with chunam	Sqr.	57·16
8. Cement pointing	„	2·91
9. Whitewashing two coats	„	57·16
10. Colour washing two coats	„	23·79
11. Flooring with 1st class Mangalore tiles over 4" concrete bed and cement pointing, etc., complete	„	8·64
12. Flooring with Cuddapah slabs over 4" concrete bed and cement pointing, etc., complete	„	2·72
13. Teakwood work wrought and put up	C. ft.	149·95
14. Roofing with 1st class Mangalore tiles with teak reepers, etc., complete	Sqr.	17·85
15. Ridge tiles set in lime mortar	R. ft.	78
16. Teakwood panelled door with frame and iron works, etc., complete	Sq. ft.	142
17. Teakwood window with inside glass shutters and outside panelled shutters ½" diameter iron bars and other iron works, etc., complete	„	88

Items of work.	*Per.*	*Quantity.*
18. Removing and refixing the existing ventilator, ...	Each	1
19. Do do do windows	„	8
20. Do do do door	„	1
21. Teakwood eve board	R. ft.	191
22. Removing and refixing the existing eve board	L. S.	Rupees.
23. Chacolate painting two coats	Sqr.	6·41
24. Wood oiling two coats	„	18·51
25. Teakwood sunshades for windows, large	Each	6
26. Do do small	„	2
26a. Teakwood screen including shutters, etc., complete	S. ft.	247
27. Teakwood sunshades for doors	Each	4
28. Teakwood ornamental finials	„	6
29. Teak wooden record rack	R. ft.	24
30. Dismantling the Bay window portion	L. S.	Rupees.

Nazir's room.

1. Removing the existing Mangalore tiled roof	Sqr.	6·05
2. Dismantling the existing wall to fix door and windows at A and B and forming the gable slope to suit hipped roof and compound wall of female dispensary, etc.	L. S.	Rupees.
3. Clearing site and levelling ground, etc.	„	„
4. Earthwork excavating foundation and filling in the same to basement level	C. yd.	6
5. Filling in foundation and basement with burnt stone in mortar ...	C. ft.	289
6. Burnt brick in mortar including bond slabs	„	644
7. Burnt stone slabs new and well dressed 6" thick	Sq. ft.	91
8. Chunam plastering	Sqr.	13·54
9. White and colour washing	„	13·54
10. Cement pointing	„	0·75
11. Flooring with Mangalore tiles over 4" concrete bed with cement pointing, etc., complete	„	2·45
12. Teakwood battened doors, double shutters with lock and key and other iron works, etc., complete	S. ft.	36
13. Teakwood battened windows with double shutters and iron bars and other iron works, etc., complete	„	48
14. Teakwood work wrought and put up	C. ft.	18·75
15. Available scantling of timber to be used as jack rafters and wall plates	L. S.	Rupees.
16. Roofing with 1st class Mangalore tiles with teak reepers, etc., complete	Sqr.	10·21
17. Cost of Mangalore tiles, available to be deducted	1,000	800
18. Mangalore tiles set in mortar	R. ft.	64
19. Fixing old Mangalpre tiles	„	30
20. Providing Mangalore ventilating tiles	No.	
21. Wood oiling two coats	Sqr	7·87
22. Teakwood eave boards, plain	R. ft.	113½
23. Chacolate painting two coats	Sqr.	3·38

Latrine.

1. Constructing a latrine	L. S.	Rupees.

R. S. NAVARATNA,
Executive Engineer.